



Ph. No. : 06553 - 256623
06553 - 256801(O)
9234302109 (M)

AGRASEN DAV PUBLIC SCHOOL

BHARECH NAGAR, DIST - RAMGARH (JHARKHAND) - 829 117

email: agrasendav.ps@gmail.com | website: www.agrasendavps.in

Affiliation No.: 3430128 School No.: 66325 PS Cell Code: JH-030

Ref. No. AGDAV/2026-27/ 246

Dated: 30.06.2026

Tender Notice

Sealed quotation are invited from the registered party / firm by 10.07.2026 for proposed work of washroom /urinals 9 nos., Area -272 sq. ft. in the school premises (junior building). Rate quoted clearly in your quotation alongwith all your terms and conditions. The detail description of the works are depicted below :

Sl. No	Particulars	Unit	Qty.	@ rate Per Sq. ft.	Total Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth, 1.5.m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed.All kinds of soil.	Cum	8.12		
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m	Cum	16.40		
3	Supplying and filling in plinth with local sand under floors, including watering, ramming consolidating and dressing complete.	Cum	0.662		
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level : 4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal.	Cum	1.20		
5	Brick work with Bricks class designation 75 in foundation and plinth in cement mortar 1 : 6 (1 Cement : Coarse sand)	Cum	9.81		
6	Brick work with common burnt clay bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : (1:6) (1 Cement : Coarse sand)	Cum	16.40		
7	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, Fillets, columnins, pillars, piers, abutments, posts and struts etc. up to floor five level excluding cost of centering, shuttering, finishing and reinforcement : (1 cement: 1.5 coarse sand: 3 graded stone aggregate 20 mm nominal size)	Cum	1.20		



AGRASEN DAV PUBLIC SCHOOL

BHARECH NAGAR, DIST - RAMGARH (JHARKHAND) - 829 117

email: agrasendav.ps@gmail.com | website: www.agrasendavps.in

Affiliation No.: 3430126 School No.: 66325 PS Cell Code: JH-030

Sl. No	Particulars	Unit	Qty.	@ rate Per Sq. ft.	Total Amount
8	Steel reinforcement for R.C.C. work, including straightening, cutting, bending, placing in position and binding all complete above plinth level. TMT Bar	Kg.	81.60		
9	Flat brick soling with bricks of class designation 75 with filling the joints with sand after leveling the ground.	Sqm.	26.80		
10	Cement concrete flooring 1:2;4 (1 cement: 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete 40 mm thick with 20 mm nominal size aggregate.	Sqm.	26.80		
11	Half brick masonry with common burnt clay bricks of class designation 7.5 in superstructure above plinth level up to floor V level. Cement mortar 1:4 (1 cement : 4 coarse sand)	Sqm.	18.40		
12	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	Kg.	530		
13	Providing and fixing pre-coated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by engineer-in-charge) 0.50 mm (+0.05%), total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade. 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-Charge. The sheet shall be fixed using self drilling / self tapping screws of size (5.5 x 55 mm) with EPDM seal, complete upto any pitch in horizontal / vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	Sqm.	27.27		
14	15mm cement plaster on the rough side of single or half thick brick wall of mix ; 1:6 (cement : 6 fine sand)	Sqm.	152.04		
15	Providing and fixing 1 st quality ceramic glazed wall tiles (300x450mm) conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	Sqm.	76.0		



AGRASEN DAV PUBLIC SCHOOL

BHARECH NAGAR, DIST - RAMGARH (JHARKHAND) - 829 117

email: agrasendav.ps@gmail.com | website: www.agrasendavps.in

Affiliation No.: 3430128 School No.: 86325 PS Cell Code: JH-030

Sl. No	Particulars	Unit	Qty.	@ rate Per Sq. ft.	Total Amount
16	Providing and laying Ceramic glazed floor tiles of size 300 x 300 mm (thickness to be specified by the manufacturer), of 1 st quality conforming to IS: 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 cement : 4 coarse sand), including pointing the joints with white cement and matching pigments etc. complete	Sqm.	27.80		
17	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machinecut for kitchen platforins, vanity counters, windows sills facias and similar locations, of required size approved shade, colour and texture laid over 20 nun thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all level 8.2.1. Raj Nagar Plain white marble / Udaipur green marble / Zebra black marble. Granite of any colour shade.	Sqm.	1.96		
18	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Conmpound) content. With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre.	Sqm.	21.62		
19	Distempering with 1 st quality acrylic distemper (Ready mix) having VOC contents less than 50 grams/litre of approved brand and manufacture to give even shade. Old work (One or more coat)	Sqm	21.62		
20	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS: 13592 Type A, including jointing with seal ring conforming to IS: 5382, leaving 10 mm gp for thermal expansion, (1) Single socketed pipes. 110 mm diameter.	Rmt	13		
21	12.41 providing and fixing on wall face unplasticised Rigid PVC rain waer pipes conforming to IS: 13592 Type A, including jointing with seal ring conforming to IS: 5382, leaving 10 mm gp for thermal expansion. (i) Single socketed pipes 75 mm dia	Rmt	10		
22	110mm bend with door	Each	4		
23	75mm bend with door	Each	4		
24	110mmx110x110mm tee with door	Each	1		
25	75x75x75mm tee with door	Each	4		



Ph. No. : 06553 - 256623
06553 - 256801(O)
9234302109 (M)

AGRASEN DAV PUBLIC SCHOOL

BHARECH NAGAR, DIST - RAMGARH (JHARKHAND) - 829 117

email: agrasendav.ps@gmail.com | website: www.agrasendavps.in

Affiliation No.: 3430128 School No.: 66325 PS Cell Code: JH-090

Sl. No	Particulars	Unit	Qty.	@ rate Per Sq. ft.	Total Amount
26	Providing and fixing white vitreous china flat back half stall urinal of size 580x380x350 CP brass flush pipe, spreaders with unions and clamps (all in C.P. brass) with waste fitting as per IS: 2556, C.I. trap with outlet grating and other couplings in C.P. brass, including painting of fittings and cutting and making good the walls and floors wherever required	Each	4		
27	Providing and fixing white vitreous china pedestal type water closet (European type W.c. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern including flush pipe with manually controlled device (handle lever conforming to IS: 7231 with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid.	Each	1		
28	Providing and fixing C.P. brass stop cock (concealed) of standard design etc complete	Each	8		
29	Providing and fixing C.P. brass bib cock of approved quality conforming to IS standard :8931	Each	2		
30	Providing and fixing s.s. pillar cock of approved quality and colour 15 mm nominal bore, 107 mm long, weighing not less than 110 gms.	Each	2		
31	Providing and fixing P.V.C. waste pipe for sink or wash basin including PVC waste fittings complete. Semi rigid pipe 32 mm dia	Each	6		
32	Providing and fixing counter top wash basin with C.I. brackets, 15mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern.	Each	2		
33	Providing and fixing beveled edge mirror of superior glass (of approved quality)	Each	2		
34	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases walls etc. 20 mm nominal outer dia Pipes	Rmt	40		
35	Providing and fixing ISI marked flush door shutters conforming to non decorative type, 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws.	Sqm.	5.355		
36	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : (Two or more coats) on New work	Sqm.	10.71		



Ph. No. : 06553 - 256623
06553 - 256801(O)
9234302109 (M)

AGRASEN DAV PUBLIC SCHOOL

BHARECH NAGAR, DIST - RAMGARH (JHARKHAND) - 829 117

email: agrasendav.ps@gmail.com | website: www.agrasendavps.in

Affiliation No.: 3430128 School No.: 66325 PS Cell Code: JH-030

Sl. No	Particulars	Unit	Qty.	@ rate Per Sq. ft.	Total Amount
37	Providing and fixing aluminium ventilator etc with 4.5 mm thick clear / blur floats glass both side habing, 12mm air gap including providing secondary scalant etc. as specification EPDM gasket perforced aluminium spacers) and discussant seatlanth (both primary drawings and directions of E.I.C.)	Sqm.	1.48		
38	Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mmm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T"	Sqm.	25.27		

Note :

1. Submit the tender alongwith copy of Labour licence, GST Number, Copy of PAN Card etc.
2. The contractor is responsible for the Safety and Security of mason, labour
3. Only standard materials to be used as specified in the tender notice
4. G.S.T. shall be payable extra if applicable as per prevailing rates.
5. Decision of Management shall be final, if any dispute raised by the contractor.

Committee Member:-

1. Mr. Sudhir Kumar Mishra, PGT (Incharge) :
2. Mr. Mousumi Banerjee, PGT
3. Mr. Krishna Kr. Bhattacharjee, TGT
4. Mr. Ranjeet Kumar Singh, TGT
5. Mr. Rajeev Kumar, UDC

(G. P. Jha)
Principal